

CITY OF BELLE GLADE – TORRY ISLAND SEAWALL PEDESTRIAN RAILING IMPROVEMENTS

EXHIBIT B – PROPOSED LAYOUT

ALUMINUM RAILING SYSTEM

RAILING SYSTEM SHALL BE CONSTRUCTED AS PER FDOT DESIGN STANDARDS/SPECIFICATIONS, LATEST EDITION(S). SEE FY 2021-22 STANDARD PLANS, INDEX 515-062 SHEETS 1-9 FOR ADDITIONAL INFORMATION.

RAILING TO INCLUDE 3/4-INCH SQUARE VERTICAL PICKETS. HANDRAIL IS ONLY REQUIRED WHEN APPLICABLE.

MATERIAL TYPE SHALL BE ALUMINUM (MILL FINISH).

RAILING SYSTEM MAY CONSIST OF WELDED MEMBERS FABRICATED IN SECTIONS. CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTING SECTIONS PER FIELD CONDITIONS.

THE APPROXIMATE PROPOSED RAILING LENGTH IS 760-LF. FINAL PAYMENT WILL BE AS PER ACTUAL INSTALLED LENGTH.

